

Vancouver in Four Days: A Personal, Practical Guide for a First-Time Visitor

Yizuo Chen

yizuo712@student.ubc.ca

yizuo.chen@mail.utoronto.ca

Abstract—This guide turns a personal collection of Vancouver notes into a realistic four-day itinerary for a first-time visitor. The route is organized geographically to reduce backtracking: downtown on Day 1; the University of British Columbia (UBC), the west-side beaches, and Queen Elizabeth Park on Day 2; and Stanley Park, SeaBus, and Capilano Suspension Bridge on Day 3. Day 4 is deliberately flexible: the visitor chooses White Rock, Victoria on Vancouver Island, Pitt Lake, or another destination according to lodging, transportation, weather, and interests. Each section explains what makes a place worth visiting, how long to allow, how to connect the stops, and which details should be checked shortly before departure. Visitor information in this edition was verified against official sources through July 23, 2026.

Index Terms—Vancouver, four-day itinerary, downtown Vancouver, UBC, Queen Elizabeth Park, Stanley Park, North Vancouver, Victoria, Pitt Lake, British Columbia travel.

I. HOW TO USE THIS GUIDE

THIS is a four-day plan, not a checklist to be completed at any cost. Vancouver rewards unhurried walking, and rain, tides, traffic, and mountain conditions can change the character of a day. The suggested time blocks are therefore flexible. Keep the order of nearby stops, but shorten or drop a stop when the weather or energy level calls for it.


The journey takes place on the traditional, ancestral, and unceded territories of the Musqueam, Squamish, and Tsleil-Waututh Nations. Read the Indigenous place names and interpretation encountered at UBC, Stanley Park, and the SeaBus terminals, and treat beaches, forests, houses of worship, and wildlife areas as living places rather than as photo sets.

A. Assumptions and Essential Preparation

The plan assumes a downtown base, ordinary walking ability, and summer-length daylight. Days 1–3 work well by walking and transit. Day 4 transportation depends on the selected destination: Pitt Lake and the mountain options are much easier with a car, while White Rock and Victoria are possible by transit but require more transfer time. Install a trip-planning app or use TransLink’s live planner, carry a contactless payment card, pack a light waterproof layer, and bring comfortable shoes. Reserve paid attractions when the date is known.

Hours and service patterns can change after publication. On the evening before each outing, verify the weather, transit alerts, attraction hours, timed-entry requirements, trail notices,

Guide prepared July 22, 2026, and revised July 23, 2026. Photographs and the route screenshot were supplied by the author.



(a) Downtown heritage architecture.



(b) Canada Place’s sail roof.

Fig. 1. A first look at downtown Vancouver and its harbour landmark.

and sunset or tide time. The official sources in the references are more authoritative than a static guide.

II. DAY 1: HARBOUR, GASTOWN, AND DOWNTOWN

A. Morning: Canada Place and the Harbour

Suggested time: 9:00–10:30 a.m. Start at Waterfront Station and walk to Canada Place. Its white sail-like roof is one of Vancouver’s clearest visual signatures. The complex is also a cruise terminal and convention, hotel, office, and visitor destination rather than a single monument [1]. Walk the west promenade and Canadian Trail for views of Burrard Inlet, Stanley Park, the North Shore mountains, working port traffic, and floatplanes [1]. This is an efficient first orientation: many places visited later can be located from the waterfront.

B. Late Morning: Gastown and Water Street

Suggested time: 10:30 a.m.–12:15 p.m. Walk east along the waterfront toward Water Street. Gastown is best experienced as a compact heritage district of brick buildings, narrow streets, restaurants, and small shops. The Steam Clock at 305 Water Street was built by Raymond Saunders in 1977. It uses both steam and an electric motor, so it should not be described as purely steam-powered; it whistles and releases steam on the hour [2]. The clock is most pleasant early, before the tight pavement around it becomes crowded.

Continue a few blocks along Water Street instead of treating the clock as a single photo stop. Daylight is best for reading the architecture; rain or blue hour brings out reflections in the brick and pavement. Stay on the busy main streets, especially after dark.

TABLE I
FOUR-DAY PLAN AT A GLANCE

Day	Theme	Core route	Best finish
1	Harbour and downtown	Canada Place → Gastown and Water Street → Vancouver Lookout → cathedrals and shopping	Dinner at Bacchus or Joe Fortes
2	Campus, beach, and gardens	Locarno/Spanish Banks → UBC Rose Garden and one museum → Queen Elizabeth Park	Quarry Gardens, city view, or Bloedel Conservatory
3	Forest and North Shore	Stanley Park seawall → Waterfront Station → SeaBus to Lonsdale Quay → bus 236 to Capilano	Return SeaBus after the North Shore light softens
4	Visitor's choice	Choose one: White Rock, Victoria, Pitt Lake, or a self-selected destination	Match the choice to lodging, transport, weather, and interests



(a) Night steam and reflections.



(b) Water Street after dark.



(c) The clock in daylight.

Fig. 2. Gastown changes dramatically between daylight and a rainy evening.



(a) Holy Rosary Cathedral.



(b) Christ Church Cathedral.

Fig. 4. Sacred architecture in the centre of downtown.



Fig. 3. Downtown towers seen from Vancouver Lookout.

C. Early Afternoon: Vancouver Lookout

Suggested time: 1:15–2:00 p.m. Across from Waterfront Station, the Vancouver Lookout provides a 360-degree orientation from Harbour Centre. Most visitors spend 30–45 minutes, and access is by elevator. The official site listed 9:30 a.m.–7:00 p.m., with the last elevator at 6:30 p.m., when checked for this edition [3]. Visibility matters more than the exact hour: on a clear day, look for the harbour, downtown peninsula, Stanley Park, UBC's direction, and Burnaby Mountain. Advance purchase is sensible in a busy period, but recheck the current hours.

D. Mid-Afternoon: Two Downtown Cathedrals

Walk first to the Cathedral of Our Lady of the Holy Rosary at 646 Richards Street. Its Gothic Revival exterior, twin spires, stained glass, and resonant interior form a calm counterpoint to the business district. The church's published opening times currently include daily access around its Mass schedule [4]. Enter quietly, remove hats where appropriate, do not photograph a service, and never treat the nave as a shortcut.

Then continue west to Christ Church Cathedral at 690 Burrard Street. It is the oldest surviving building in downtown Vancouver and a Class A heritage building, with cedar ceiling planks, stained glass, regimental history, and a modern glass bell spire [5]. Queen Elizabeth II visited the cathedral in 1951, a detail preserved in the cathedral's own memorial history [6]. Published general visiting hours were Monday to Friday, 10:00 a.m.–4:00 p.m., excluding statutory holidays [7]. If Day 1 falls on a weekend, enjoy the exterior and move the interior visit to a weekday.




Fig. 5. Interior lighting and vaulting at Holy Rosary Cathedral.

E. Shopping and Dinner

For concentrated shopping, continue to CF Pacific Centre and Holt Renfrew.

- **Bacchus Restaurant & Lounge, Wedgewood Hotel:** formal, quiet, and central. Bacchus is listed in the Michelin Guide as a contemporary French restaurant; a Michelin listing should not be confused with a Michelin star [8].
- **Joe Fortes Seafood & Chop House:** a lively Vancouver institution near Robson Street, known for seafood, steaks, and a large wine list. The restaurant publishes daily 11:00 a.m.–11:00 p.m. hours, but a reservation is wise [9].

III. DAY 2: UBC, WESTERN BEACHES, AND QUEEN ELIZABETH PARK

A. Early Morning: Locarno Beach and Spanish Banks


Suggested time: 8:00–9:00 a.m. Begin on the west side before the campus museums open. Locarno is the quieter, tree-backed choice; it is a designated quiet beach with washrooms, picnic tables, volleyball courts, and seasonal lifeguards [15]. Spanish Banks is broader and more dramatic at low tide, when the water can retreat far across the flats. Its east, west, and extension areas have different amenities and designated off-leash or kiteboarding zones [16]. Check the tide table if exposed sand is important, do not harvest shellfish, and read the current parking signs.

Keep this stop to about an hour. Locarno and Spanish Banks are adjacent parts of one shoreline experience, not two separate expeditions. A simple breakfast or coffee is enough; the purpose is fresh air and the early view before UBC.

B. Late Morning and Lunch: A Focused UBC Visit

Suggested time: 9:30 a.m.–1:30 p.m. Begin with the Rose Garden at 6301 Crescent Road. From June to September, more than a dozen types of roses bloom above ocean and mountain views; the garden is free [10]. Pair it with the nearby ocean outlook and then choose *one* museum.

MOA is the cultural choice. Its Great Hall, monumental carvings, visible storage, and outdoor works reward at least 90 minutes. Approach the displays as living cultural knowledge, not generic “artifacts,” and read the community and artist identifications. MOA’s schedule is generally 10:00 a.m.–5:00



(a) City skyline from the beach.




(b) Sunset colours can also appear at day's end.

Fig. 6. The western beaches provide a calm beginning to the revised UBC day.



(a) UBC arrival photograph.



(b) Campus architecture and gardens.

Fig. 7. UBC's Point Grey campus combines formal spaces with broad views.



(a) Beaty's blue whale skeleton.



(b) MOA's Great Hall.

Fig. 8. Choose one UBC museum: natural history at Beaty or human culture at MOA.

p.m., with Thursday evening hours and a seasonal Monday closure; verify the selected date [11]. The Beaty Biodiversity Museum is the natural-history choice. Its signature 26-m blue whale skeleton introduces more than 500 exhibits and roughly two million research specimens [13]. Its summer 2026 schedule listed daily 10:00 a.m.–5:00 p.m. hours, with statutory-holiday exceptions [14].

After the museum, take a compact route through the UBC Bookstore and Irving K. Barber Learning Centre (IKB). IKB combines study areas, the Chapman Learning Commons, special collections, archives, and public educational resources; some services and rooms are restricted [12]. Eat a quick campus lunch and leave by about 1:30 p.m. Trying to complete both museums will crowd out Queen Elizabeth Park.

C. Afternoon: Queen Elizabeth Park

Suggested time: 2:30–5:30 p.m. Continue to Queen Elizabeth Park, near the BC Children's Hospital area at Cambie Street and West 33rd Avenue. Allow extra transfer time from



Fig. 9. Stanley Park is a sequence of shoreline, skyline, and forest views.

UBC. The park is also near the King Edward and Oakridge–41st Canada Line stations [17].

Start at the summit plaza for the city and North Shore mountain view, then descend into the former quarry. The free garden circuit is only about 0.41 km, but the Quarry Gardens, rose beds, fountains, public art, and viewpoints easily fill 60–90 minutes. Marked garden routes are wheelchair accessible, although some sections have a significant incline [18].

For a paid indoor finish, enter Bloedel Conservatory. The heritage dome contains more than 500 exotic plants, koi, and free-flying tropical birds. From May to Labour Day the published 2026 hours were 10:00 a.m.–7:00 p.m.; other seasons close earlier, and last entry is 15 minutes before closing [19]. It is warm and humid inside, so carry rather than wear a heavy outer layer. If time remains, finish at the viewpoint or reserve an early dinner at Seasons in the Park. This stop replaces the old beach-at-sunset finish and keeps the afternoon close to the central Vancouver and BC Children’s Hospital area.

IV. DAY 3: STANLEY PARK, SEABUS, AND CAPILANO


A. Morning: Stanley Park and the Seawall

Suggested time: 8:30 a.m.–12:00 p.m. Enter Stanley Park early. The full seawall loop is about 10 km, so allow 2.5–4 hours depending on stops and whether the route is walked or cycled [20]. The changing views are the point: Coal Harbour, the working port, Brockton Point, the Lions Gate Bridge, Siwash Rock, English Bay, and forest edges.

Walkers and cyclists use different lanes and directions in some areas; follow the signs and avoid stepping into the bicycle lane for photographs. If 10 km is too much, make a shorter loop around Coal Harbour and Brockton Point, then save energy for Capilano. A small sea star or shell should be observed and returned exactly where found; do not remove living shoreline organisms.

B. Afternoon: SeaBus to North Vancouver

Return to Waterfront Station and take the SeaBus to Lonsdale Quay. The crossing is a useful attraction in its own right: sit beside a window for a water-level view back to the downtown skyline and Canada Place. SeaBus commonly operates every 10–15 minutes during busier periods and less frequently late in the evening, but use the current schedule and service alerts rather than memorizing a departure [21].



(a) Route snapshot supplied with the notes.

(b) Downtown seen from the water.

Fig. 10. The SeaBus connects Waterfront Station and Lonsdale Quay.



Fig. 11. Capilano Suspension Bridge above the temperate rainforest.

Have a quick lunch near Lonsdale Quay, then board bus 236 toward Grouse Mountain and get off at Capilano Suspension Bridge. This is the attraction’s official transit route from downtown via SeaBus [22].

C. Late Afternoon: Capilano Suspension Bridge Park

Allow 2.5–3 hours for the suspension bridge, Treetops Adventure, Cliffwalk, and interpretation. This is a ticketed attraction with timed entry. Summer 2026 hours were listed as 8:30 a.m.–8:00 p.m.; tickets, seasonal hours, and access rules should be rechecked [23]. The bridge, Cliffwalk, and Treetops Adventure are not wheelchair accessible.

The park can feel crowded at midday. A later entry usually gives softer light, and the official downtown shuttle is an alternative to SeaBus and bus 236. Return by bus 236 to Lonsdale Quay, then take the SeaBus back. The second crossing is especially good around sunset or after the city lights appear.

V. DAY 4: CHOOSE THE RIGHT FINAL DAY

Day 4 is a multiple-choice day rather than a fixed itinerary. Choose exactly one principal destination after considering where the visitor is staying, the available vehicle or transit connections, the weather, and the kind of day the group




Fig. 12. White Rock is the relaxed coastal choice for Day 4.

actually wants. Do not combine Choices A–C merely to collect names.

- Choice A: White Rock** for an easier seaside day with a promenade, pier, restaurants, and attractive evening reflections.
- Choice B: Victoria on Vancouver Island** for the most ambitious option: a very early start, ferry travel, harbour architecture, and one major museum.
- Choice C: Pitt Lake** for Yizuo’s personal favourite: wetlands, mountains, wildlife watching, quiet, and landscape photography.
- Choice D: A self-selected destination** when another place better suits the visitor’s lodging, mobility, weather, or strongest interest.

A. White Rock—Seaside, Food, and an Easy Pace

Choose White Rock when the visitor is staying in South Vancouver, Richmond, Delta, Surrey, or anywhere that makes the southern trip more convenient than crossing the region toward Pitt Lake. It also suits a group that prefers a long waterfront walk and restaurant meal to a remote natural setting.

The historic wooden pier extends about 470 m into Semiahmoo Bay, and the promenade connects the east and west beaches [24]. Begin around late morning, have lunch near Marine Drive, walk the promenade without rushing, and stay for blue hour if the weather is clear. Reflections from the hillside homes make the water particularly attractive after dark. Observe current pier rules: cycling, skating, smoking, and dogs on the pier are prohibited.

B. Victoria on Vancouver Island—A Long Day Trip

The accurate name is *Victoria on Vancouver Island*, not “Victoria Island.” Choose it for heritage streets, the Inner Harbour, the Parliament Buildings, and museums—and only when everyone accepts a long travel day. BC Ferries connects Tsawwassen with Swartz Bay in about 1 hour 35 minutes; Tsawwassen is itself about 36 km from downtown Vancouver, and Swartz Bay is north of central Victoria [25]. Terminal transfers and check-in therefore make the door-to-door journey much longer than the sailing.

Reserve the ferry when possible, leave very early, and recheck same-day service notices. Once downtown, keep the visit compact: Inner Harbour, the Parliament grounds, Government Street/Old Town, and either the Royal BC Museum




Fig. 13. Pitt Lake rewards patience beyond the conventional golden hour.

or a long lunch. Destination Greater Victoria notes that one day leaves little time for the full island experience [26]; do not automatically add Butchart Gardens to an already compressed downtown visit. This option is most sensible for a visitor staying south of downtown, travelling by an organized tour, or willing to treat transportation as part of the experience.

C. Pitt Lake—Quiet Landscape and Photography

Pitt Lake is Yizuo’s favourite place in the region. It can feel spacious and still in daylight, graphic at sunset, and almost otherworldly under moonlight. Every season and hour changes the composition of water, marsh, mountain, and sky. The Pitt-Addington Marsh Wildlife Management Area lies at the south end of the lake, about 60 km east-northeast of Vancouver. Its wetlands support more than 200 bird species and 29 mammal species; habitat comes first and recreation second [27].

Drive toward Grant Narrows and keep the day intentionally loose. Arrive before lunch, read the access and shoreline signs, take a short low-impact walk, watch for birds, picnic only where permitted, and pack out every item. Stay through late afternoon if conditions are stable, but leave enough light for the access road unless night driving is deliberate and comfortable.

Do not improvise a remote paddle. Wind and tidal influence can make the large lake hazardous, and a canoe crossing toward Widgeon Creek requires separate equipment, skills, and planning. Stay out of closed dyke and habitat areas, keep distance from wildlife, and do not rely on strong mobile coverage. On the return, the notebook’s Eastern Pearl Seafood Restaurant in Port Coquitlam is an optional family-style Chinese seafood or dim-sum stop; confirm its current name, hours, and reservation policy before driving there.

D. Build a Day Around the Visitor

Use the lodging location as the first filter and the visitor’s strongest interest as the second. Someone without a car may prefer one transit-friendly neighbourhood, waterfront, museum, or food district. Someone staying farther south or east may find White Rock or Pitt Lake more efficient than returning through downtown. A garden lover may choose VanDusen; a food-focused visitor may prefer Richmond or Steveston; and an experienced, prepared hiker may choose one of the mountain options below if current conditions permit.

A good custom day needs only one anchor activity, one flexible secondary stop, and one meal. Check the actual door-to-door travel time from the accommodation, not just the



(a) Abbey sanctuary.

(b) Stained glass and timber structure.

Fig. 14. Westminster Abbey is a place of worship and sacred silence.

distance on a regional map. If transportation consumes more time than the destination, choose something closer and enjoy it properly.

VI. LONGER OPTIONAL EXCURSIONS

The remaining notes describe worthwhile places, but most require enough travel or hiking to occupy a full day. Combining them with another Day 4 choice would make the visit rushed and, for the mountain trips, potentially unsafe.

A. Westminster Abbey: Quiet Architecture and a Viewpoint


Westminster Abbey in Mission is a Benedictine monastery, not a recreational park. It works as a contemplative half-day drive for architecture, silence, the gardens, and the viewpoint toward the Fraser Valley and Mount Baker. The Abbey Church and paths have specific visitor periods. Current guidance asks for absolute silence in the church, modest clothing, no photographs during services, no pets, and no picnics [28], [29]. Check the schedule before the long drive and respect all boundary signs.

B. Lindeman Lake: A Dedicated Hiking Day

Lindeman Lake lies in Sxotsaqel/Chilliwack Lake Park, well beyond Vancouver. The official route is about 3.4 km return, but the rocky, root-filled climb and long drive make it a full excursion rather than a casual urban walk. BC Parks listed the trail as open when this guide was prepared; visitors should still check the South Fraser trail report, carry water and layers, and leave no food or waste [30]. Never continue to Greendrop Lake merely because the map distance looks short.

C. Garibaldi Park: Spectacular but Demanding

Garibaldi Park is a full mountain day requiring an early start, capable hikers, proper footwear, food, water, weather awareness, and a clear turnaround time. Do not choose a route from photographs alone. In summer 2026, vehicle day-use passes were required on specified days at the Diamond Head, Rubble Creek, and Cheakamus Lake trailheads, with different rules by trailhead [31]. Snow and closures can persist at elevation even when Vancouver is warm.




(a) Lindeman Lake.

(b) Alpine water in Garibaldi Park.



(c) Mountain approach and driftwood.

Fig. 15. Lindeman and Garibaldi are destination hikes, not spare-time stops.



(a) Still water at Manning Park.

(b) Forest bridge.

Fig. 16. Manning Park ranges from gentle lakeside scenery to remote trails.

D. E.C. Manning Park: A Separate Road Trip

Manning Park is best reserved for a later trip or used as a complete Day 4 replacement. It offers everything from short nature walks to backcountry routes, lakes, wildlife, and high-elevation viewpoints. Conditions vary greatly by elevation, and mobile service is absent in the park. In this edition, BC Parks reported the Blackwall Road closed at Cascade Lookout and advised visitors to consult the current trail report [32]. A simple first visit might combine Lightning Lake with an easy signed trail rather than an ambitious summit.

VII. WEATHER, ACCESSIBILITY, AND BACKUP LOGIC

A. Rain

Light rain suits Gastown, the cathedrals, MOA, Beaty, IKB, Bloedel Conservatory, and downtown dining. Move the UBC museums or other interiors to the wettest period. Avoid exposed lookouts when clouds erase the view, and never let a prepaid ticket pressure the group into unsafe outdoor conditions.

B. Mobility and Fatigue

The full Stanley Park seawall and the revised UBC–Queen Elizabeth Park day contain substantial walking and inclines.

Shorten Stanley Park to Coal Harbour/Brockton Point, choose one UBC museum, and use the accessible marked garden route at Queen Elizabeth Park if necessary. Vancouver Lookout, Bloedel, and the SeaBus are comparatively easy-access viewing experiences. Capilano explicitly states that its bridge, Treetops, and Cliffwalk are not wheelchair accessible [23]. Confirm accessibility directly with every venue for individual needs.

C. A Useful Priority Rule

If time is lost, protect one signature experience from each day:

- Day 1: Canada Place to Gastown on foot;
- Day 2: one UBC museum and the Queen Elizabeth Park viewpoint;
- Day 3: Stanley Park plus the SeaBus crossing; and
- Day 4: one well-chosen destination, with enough time to enjoy it.

The rest can be moved, shortened, or saved for another visit.

VIII. CONCLUSION

The strongest four-day Vancouver visit alternates city and landscape: harbour and heritage; university, beach, and garden; seawall and rainforest; then a final day selected for the visitor rather than imposed by a universal list. The first three days establish Vancouver's major contrasts, while Day 4 adapts to location, transportation, weather, and personal interest.

Most importantly, leave space to look. Canada Place is more than its sails; Gastown is more than a clock; UBC is more than a campus sign; and the right final destination is the one the visitor can experience without rushing. The best version of this trip will contain a few pauses that never appear on an itinerary.

REFERENCES

- [1] Destination Vancouver, "Canada Place." [Online]. Available: <https://www.destinationvancouver.com/things-to-do/listings/canada-place>. Accessed: Jul. 22, 2026.
- [2] Destination Vancouver, "Steamclock." [Online]. Available: <https://www.destinationvancouver.com/things-to-do/listings/steamclock>. Accessed: Jul. 22, 2026.
- [3] Vancouver Lookout, "Plan Your Visit." [Online]. Available: <https://vancouverlookout.com/wp/hours/>. Accessed: Jul. 22, 2026.
- [4] Cathedral of Our Lady of the Holy Rosary, "Welcome to the Cathedral." [Online]. Available: <https://www.holyrosarycathedral.org/>. Accessed: Jul. 22, 2026.
- [5] Christ Church Cathedral, "Architecture & Heritage." [Online]. Available: <https://www.thecathedral.ca/programs/architecture-heritage>. Accessed: Jul. 22, 2026.
- [6] Christ Church Cathedral, "Remembering Queen Elizabeth at the Cathedral," Sep. 8, 2022. [Online]. Available: <https://www.thecathedral.ca/news/remembering-queen-elizabeth-at-the-cathedral>. Accessed: Jul. 22, 2026.
- [7] Christ Church Cathedral, "About." [Online]. Available: <https://www.thecathedral.ca/pages/about>. Accessed: Jul. 22, 2026.
- [8] Michelin Guide, "Bacchus-Vancouver." [Online]. Available: <https://guide.michelin.com/en/british-columbia/ca-vancouver/restaurant/bacchus-1199004>. Accessed: Jul. 22, 2026.
- [9] Joe Fortes Seafood & Chop House, "Welcome to Joe Fortes." [Online]. Available: <https://www.joefortes.ca/>. Accessed: Jul. 22, 2026.
- [10] The University of British Columbia, "UBC Rose Garden." [Online]. Available: <https://visit.ubc.ca/see-and-do/gardens-and-nature/ubc-rose-garden/>. Accessed: Jul. 22, 2026.
- [11] Museum of Anthropology at UBC, "Visit MOA." [Online]. Available: <https://moa.ubc.ca/>. Accessed: Jul. 22, 2026.
- [12] Irving K. Barber Learning Centre, "Home." [Online]. Available: <https://ikblc.ubc.ca/>. Accessed: Jul. 22, 2026.
- [13] Beaty Biodiversity Museum, "About." [Online]. Available: <https://beatymuseum.ubc.ca/visit/about/>. Accessed: Jul. 22, 2026.
- [14] Beaty Biodiversity Museum, "Hours & Directions." [Online]. Available: <https://beatymuseum.ubc.ca/visit/about/hours/>. Accessed: Jul. 22, 2026.
- [15] City of Vancouver, "Locarno Beach." [Online]. Available: <https://vancouver.ca/parks-recreation-culture/locarno-beach.aspx>. Accessed: Jul. 22, 2026.
- [16] City of Vancouver, "Spanish Banks Beach." [Online]. Available: <https://vancouver.ca/parks-recreation-culture/spanish-bank-beach.aspx>. Accessed: Jul. 22, 2026.
- [17] City of Vancouver, "Getting to Queen Elizabeth Park." [Online]. Available: <https://vancouver.ca/parks-recreation-culture/queen-elizabeth-park-directions.aspx>. Accessed: Jul. 23, 2026.
- [18] City of Vancouver, "Queen Elizabeth Garden Walk." [Online]. Available: <https://vancouver.ca/parks-recreation-culture/queen-elizabeth-garden.aspx>. Accessed: Jul. 23, 2026.
- [19] City of Vancouver, "Bloedel Conservatory." [Online]. Available: <https://vancouver.ca/parks-recreation-culture/bloedel-conservatory.aspx>. Accessed: Jul. 23, 2026.
- [20] City of Vancouver, "Stanley Park Seawall Walk." [Online]. Available: <https://vancouver.ca/parks-recreation-culture/stanley-park-seawall.aspx>. Accessed: Jul. 22, 2026.
- [21] TransLink, "SeaBus Schedules." [Online]. Available: <https://www.translink.ca/schedules-and-maps/seabus>. Accessed: Jul. 22, 2026.
- [22] Capilano Suspension Bridge Park, "Directions." [Online]. Available: <https://www.capbridge.com/getting-here/>. Accessed: Jul. 22, 2026.
- [23] Capilano Suspension Bridge Park, "Official Tickets and Hours." [Online]. Available: <https://www.capbridge.com/tickets-and-hours/>. Accessed: Jul. 22, 2026.
- [24] City of White Rock, "Pier & Promenade." [Online]. Available: <https://www.whiterockcity.ca/401/Pier-Promenade>. Accessed: Jul. 22, 2026.
- [25] BC Ferries, "Vancouver (Tsawwassen)-Victoria (Swartz Bay)." [Online]. Available: <https://www.bcferries.com/routes-fares/schedules/daily/TSA-SWB>. Accessed: Jul. 23, 2026.
- [26] Destination Greater Victoria, "Itineraries." [Online]. Available: <https://www.destinationgreatervictoria.com/travel-trade/itineraries>. Accessed: Jul. 23, 2026.
- [27] Province of British Columbia, "Pitt-Addington Marsh Wildlife Management Area." [Online]. Available: <https://www2.gov.bc.ca/gov/content/environment/plants-animals-ecosystems/wildlife/wildlife-habitats/conservation-lands/wma/wmas-list/pitt-addington-marsh>. Accessed: Jul. 22, 2026.
- [28] Westminster Abbey, "Visiting Hours." [Online]. Available: <https://westminsterabbey.ca/visit/visiting-hours/>. Accessed: Jul. 22, 2026.
- [29] Westminster Abbey, "Visiting Guidelines." [Online]. Available: <https://westminsterabbey.ca/visit/visiting-guidelines/>. Accessed: Jul. 22, 2026.
- [30] BC Parks, "Sxotsaqel/Chilliwack Lake Park." [Online]. Available: <https://bcparks.ca/sxotsaqel-chilliwack-lake-park/>. Accessed: Jul. 22, 2026.
- [31] BC Parks, "Day-Use Passes." [Online]. Available: <https://bcparks.ca/reservations/day-use-passes/>. Accessed: Jul. 22, 2026.
- [32] BC Parks, "E.C. Manning Park." [Online]. Available: <https://bcparks.ca/ec-manning-park/>. Accessed: Jul. 22, 2026.